BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Name of work: Estimate for Providing Road markings to main and cross roads of ward no. 08 Kodigehalli

Estimate Cost Rs. 500000.00

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5. **No. 147/ Item No. 21.2/ PWD SR 2015-16**	Sqm							
			1	2720.00	7.00		19040.00		
							19040.00	3.24	**61690.00**
	Basic Rate	3.00							
	Area Weightage @8%	0.24							
	Total	**3.24**							
2	KSRRB M800-13: Road marking with hot applied thermoplastic compound with reflect rising glass beads on bituminous surface-providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface to level, uniform and free from streaks and holes complete as per specifications. MORTH specification No. 803, **No. 168/ Item No. 24.15PWD SR 2015-16**	Sqm							
			2	2720.00	0.10		544.00		
	2600/3=933		907	3.00	0.10		272.10		
							816.10	473.04	**386048.00**
	Basic Rate	438.00							
	Area Weightage @ 8%	35.04							
	Total	**473.04**							
3	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading.	Cum							
			Qty. Vide Item No. 1				**375.00**	123.20	**46200.00**
4	Sub Total								**493938.00**

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
10	Third Party Inspection Charges @ 1%								4939.00
6	Add for unforseen and rounding off	L/S							1123.00
								Total	500000.00

(Rupees Five Lakhs Only)

Certificate:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per PWD SR of 2015-16.
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.

Junior/Assistant Engineer
Ward No. 08

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Kodigehalli Sub Division

14/12

Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division

14/12

ADMINISTRATIVE APPROVAL

Accorded For Rs. 5.00L

Head of A/c. P-1771

Div. Ref. No. 62/16-17 Date. 14/12/16

AE

EE(BTP) 14/12

TECHNICAL SANCTION

Accorded For Rs. 5.00L

Head of A/c. P-1771

Div. Ref. No. 76/16-17 Date. 14/12/16

AE

EE(BTP) 14/12